BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/02/2020-21 Date: 10.06.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT42806

SCHEDULE -B

Name of Work: Providing Rain Water Harvesting in selected area of Jalahalli in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1004.40	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. in hard soil.	Cum	493.00	Rupees Four Hundred Ninety Three Only
2	251.10	Providing Nominal 100mm size stone aggrigates	Cum	1035.00	Rupees One Thousand Thirty Five Only
3	251.10	Providing Nominal 40mm size stone aggrigates	Cum	1144.00	Rupees One Thousand One Hundred Forty Four Only
4	251.10	Providing Nominal 20mm size stone aggrigates	Cum	1144.00	Rupees One Thousand One Hundred Forty Four Only
5	251.10	Providing And filling sand in foundation to required deapth for subsoilo treatment includiung watering ramming with all lead and lift complete as pper specification	Cum	2288.00	Rupees Two Thousand Two Hundred Eighty Eight Only
6	7000.00	Providing And fixing ms grill work for windows and ventilators using ms flats or ms square rods or combination of ms flats and square rods as per approved design drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer cost of materials fixtures, labours, and complete as per specifications	Kg	106.00	Rupees One Hundred Six Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP